Name: Davonn Escobilla	Date Performed: 08/12/2022
Course/Section: CPE31S24	Date Submitted: 08/12/2022
Instructor: Dr. Jonathan Taylar	Semester and SY: 1st, 2022 - 2023
Activity 14: OpenStack Installation (Keystone, Glance, Nova)	

1. Objectives

Create a workflow to install OpenStack using Ansible as your Infrastructure as Code (IaC).

2. Intended Learning Outcomes

- 1. Analyze the advantages and disadvantages of cloud services
- 2. Evaluate different Cloud deployment and service models
- 3. Create a workflow to install and configure OpenStack base services using Ansible as documentation and execution.

3. Resources

Oracle VirtualBox (Hypervisor)


1x Ubuntu VM or Centos VM

4. Tasks

- 1. Create a new repository for this activity.
- 2. Create a playbook that converts the steps in the following items in https://docs.openstack.org/install-guide/
 - a. Keystone (Identity Service)
 - b. Glance (Imaging Service)
 - c. Nova (Compute Service)
 - d. Create different plays in installing per server type (controller, compute etc.) and identify it as a group in the Inventory file.
 - e. Add, commit and push it to your GitHub repo.

5. Output (screenshots and explanations)

First is to create the repository and clone it into the managed node.



Next step, create ansible.cf for configuration and inventory for control nodes.

```
GNU nano 6.2 ansible.cfg *

[defaults]
deprecation_warnings=False
command_warnings=False
inventory=inventory
private_key_file = ~/.ssh/ansible
```

Group the ip addresses.

```
GNU nano 6.2 inventory *

[compute]
192.168.56.106
[controller]
192.168.56.106
```

Next step, create roles for each installation package.

```
cdavonn@workstation:~/Act14$ cd roles
davonn@workstation:~/Act14/roles$ mkdir -p {Keystone,Glance,Nova}/tasks
davonn@workstation:~/Act14/roles$ tree

Glance
Lasks
Keystone
Lasks
Nova
Lasks
Odirectories, 0 files
```

After creating roles, configure the yml to install all basic tasks and the packages on each roles.

```
davonn@workstation: ~/Act14
 J∓l
 GNU nano 6.2
                                     Act14.yml
- hosts: all
 become: true
 pre_tasks:
    name: Install updates Ubuntu
    tags: always
    apt:
      upgrade: dist
      update_cache: yes
    changed when: false
    when: ansible_distribution == "Ubuntu"
hosts: controller
 become: true
 roles:
   - Keystone
- hosts: compute
 become: true
 roles:
   - Nova
   - Glance
```


Next is the main.yml on each task.

Keystone

Glance davonn@workstation: ~/Act14/roles/Glance/tasks GNU nano 6.2 main.yml name: Install the OpenStack Glance apt: name: glance state: latest update_cache: yes when: ansible_distribution == "Ubuntu"

Nova

After creating main.yml on each role, run the ansible playbook.



```
ſŦ
                     davonn@workstation: ~/Act14
                                          Q = - -
ok: [192.168.56.106]
TASK [Keystone : Install the OpenStack Keystone] *******************
TASK [Nova : Install the OpenStack Nova] **************************
TASK [Glance : Install the OpenStack Glance] ***********************
changed: [192.168.56.106]
192.168.56.106
                           changed=2 unreachable=0
                                                 failed=0
skipped=0
        rescued=0
                  ignored=0
Output:
davonn@server3:~$ systemctl status glance-api.service
glance-api.service - OpenStack Image Service API
    Loaded: loaded (/lib/systemd/system/glance-api.service; enabled; vendor p>
    Active: active (running) since Thu 2022-12-08 19:58:09 PST; 1min 46s ago
     Docs: man:glance-api(1)
  Main PID: 60746 (glance-api)
     Tasks: 2 (limit: 1635)
    Memory: 149.8M
      CPU: 3.335s
    CGroup: /system.slice/glance-api.service
           -60746 /usr/bin/python3 /usr/bin/glance-api --config-file=/etc/g>
          -61744 /usr/bin/python3 /usr/bin/glance-api --config-file=/etc/g>
Dec 08 19:58:09 server3 systemd[1]: Started OpenStack Image Service API.
```

```
davonn@server3:~$ systemctl status apache2.service
apache2.service - The Apache HTTP Server
     Loaded: loaded (/lib/systemd/system/apache2.service; enabled; vendor pres>
     Active: active (running) since Thu 2022-12-08 19:57:39 PST; 2min 56s ago
       Docs: https://httpd.apache.org/docs/2.4/
   Main PID: 58963 (apache2)
      Tasks: 26 (limit: 1635)
     Memory: 52.7M
        CPU: 599ms
     CGroup: /system.slice/apache2.service
              -58963 /usr/sbin/apache2 -k start
              -59037 "(wsgi:keystone-pu" -k start
               -59038 "(wsgi:keystone-pu" -k start
              -59039 "(wsgi:keystone-pu" -k start
              -59040 "(wsgi:keystone-pu" -k start
               -59041 "(wsgi:keystone-pu" -k start
               -59042 /usr/sbin/apache2 -k start
              -59043 /usr/sbin/apache2 -k start
               -59044 /usr/sbin/apache2 -k start
              -59045 /usr/sbin/apache2 -k start
             -59046 /usr/sbin/apache2 -k start
Dec 08 19:57:39 server3 systemd[1]: apache2.service: Deactivated successfully.
Dec 08 19:57:39 server3 systemd[1]: apache2.service: Unit process 58718 (apach>
Dec 08 19:57:39 server3 systemd[1]: apache2.service: Unit process 58719 (apach>
Dec 08 19:57:39 server3 systemd[1]: Stopped The Apache HTTP Server.
Dec 08 19:57:39 server3 systemd[1]: Starting The Apache HTTP Server...
Dec 08 19:57:39 server3 apachectl[58962]: AH00558: apache2: Could not reliably>
Dec 08 19:57:39 server3 systemd[1]: Started The Apache HTTP Server.
davonn@server3:~$ systemctl status nova-compute.service
nova-compute.service - OpenStack Compute
     Loaded: loaded (/lib/systemd/system/nova-compute.service; enabled; vendor>
     Active: active (running) since Thu 2022-12-08 19:28:27 PST; 32min ago
  Main PID: 2573 (nova-compute)
      Tasks: 2 (limit: 1635)
     Memory: 73.2M
        CPU: 3.409s
     CGroup: /system.slice/nova-compute.service
              -2573 /usr/bin/python3 /usr/bin/nova-compute --config-file=/etc/
Dec 08 19:28:27 server3 systemd[1]: Started OpenStack Compute.
Dec 08 19:29:32 server3 nova-compute[2573]: Modules with known eventlet monkey>
```

Lastly, save the work on github.

```
Ħ
                             davonn@workstation: ~/Act14
                                                           Q.
davonn@workstation:~/Act14$ git add -A
davonn@workstation:~/Act14$ git commit -m "Activity 14"
[main (root-commit) 808200d] Activity 14
 6 files changed, 56 insertions(+)
 create mode 100644 Act14.yml
 create mode 100644 ansible.cfg
 create mode 100644 inventory
 create mode 100644 roles/Glance/tasks/main.yml
 create mode 100644 roles/Keystone/tasks/main.yml
 create mode 100644 roles/Nova/tasks/main.yml
davonn@workstation:~/Act14$ git push
Enumerating objects: 15, done.
Counting objects: 100% (15/15), done.
Compressing objects: 100% (9/9), done.
Writing objects: 100% (15/15), 1.33 KiB | 681.00 KiB/s, done.
Total 15 (delta 1), reused 0 (delta 0), pack-reused 0
remote: Resolving deltas: 100% (1/1), done.
To github.com:DavonnEscobilla/Act14.git
 * [new branch]
                     main -> main
davonn@workstation:~/Act14$
```

Reflections:

Answer the following:

Describe Keystone, Glance and Nova services
 Keystone is a service that gives API client authentication. While Glance, provides
 service to discover, register, and retrieve virtual machine images. Nova compute
 service is to provide scalability on a massive scale and have access to compute
 resources in a self service way.

Conclusions:

Upon performing the activity, there are no struggles on receiving errors since there is a provided manual or code to enter into the configuration. The only challenge here is the management of each task in every role. Using the previous knowledge about creating roles, the activity is performed efficiently and without errors.